

Submittal Data Sheet

absolute comfort

| Project Name: | |
|---------------|---|
| Location: | A |
| Engineer: | D |
| Submitted to: | C |
| Submitted by: | A |
| Reference: | D |
| | |

| pproval: | |
|---------------|---|
| Pate: | |
| Construction: | |
| Init #: | _ |
| Prawing #: | |
| | |

Performance

| Indoor Unit Model No: | FXHQ36MVJU |
|--------------------------------------|------------|
| Cooling Capacity (Btu/hr): | 36000 |
| Sensible Capacity (Btu/hr): | 25100 |
| Cooling Input Power (kW): | 0.161 |
| Heating Capacity (Btu/hr): | 40000 |
| Heating Input Power (kW): | 0.161 |
| Nominal Ext Static Pressure (inH2O): | 0 |
| Max Ext Static Pressure (inH2O): | 0 |

| Indoor Unit Type: | Ceiling Suspended |
|-----------------------------|--------------------------|
| | Indoor: 80°F DB/67°F WB |
| Cooling Nominal Conditions | Outdoor: 95°F DB/75°F WB |
| Llasting Marring Conditions | Indoor: 70°F DB/60°F WB |
| Heating Nominal Conditions | Outdoor: 47°F DB/43°F WB |
| Nominal Piping Length | 25 |
| Nominal Height Separation | 0 |

Indoor Unit Details

| Power Supply (V/Hz/Ph:) | 208-230/60/1ph |
|----------------------------|-----------------------|
| Power Supply Connections: | L1, L2, Ground |
| Min. Circuit Amps MCA (A): | 1.4 |
| Max. Fusible Amps MFA (A): | 15 |
| Dimensions (HxWxD): | 7-11/16x62-5/8x26-3/4 |
| Panel (HxWxD): | N/A |
| Net Weight (lbs): | 90 |
| Weight with Panel (lbs): | |

| Airflow Rate (CFM wet coil) | 830//670 |
|--------------------------------|----------|
| Moisture Removal (pt/h): | |
| Gas Pipe Connection (inch): | 5/8 |
| Liquid Pipe Connection (inch): | 3/8 |
| Condensate Connection (inch): | 1 |
| Sound Pressure Level (dBA): | 46 |
| Sound Power Level (dBA): | |

Appearance - Indoor Unit






Submittal Data Sheet

| Project Name: | |
|---------------|---------|
| Location: | Approva |
| Engineer: | Date: |
| Submitted to: | Constru |
| Submitted by: | Unit #: |
| Reference: | Drawing |

| Approval: | |
|---------------|--|
| Date: | |
| Construction: | |
| Unit #: | |
| Drawing #: | |

Dimensional Drawing - Indoor Unit

Daikin AC TRL Generated Submittal Data



Daikin AC (Americas), Inc., 1645 Wallace Drive - Suite 110, Carrollton, TX 75006



Submittal Data Sheet

| Project Name: | |
|---------------|---------------|
| Location: | Approval: |
| Engineer: | Date: |
| Submitted to: | Construction: |
| Submitted by: | Unit #: |
| Reference: | Drawing #: |

<u>Notes</u>

Daikin AC TRL Generated Submittal Data

Std U.S. Warranty: 6yrs Compressor, 1yrs Parts, 1yr Limited Labor

Daikin AC (Americas), Inc., 1645 Wallace Drive - Suite 110, Carrollton, TX 75006